

Green Mt. Paving project, From foot of Champion Hill Road to approx.. West Range road  
\$198,410.60 for paving and \$65,000.00 for earth work.

Delineated items on earth work are:

1. box cut to 2 feet approx. by 11 feet wide by 75 feet long total.
2. 900 feet of ditching
3. 4 culvert replacements, one possible review by engineer
4. 1 possible new culvert
5. General preparation of the road for paving
6. Shoulder work after paving.

Paving will include reclamation of existing surface.

Total proposed appropriation: \$263,410.60

As discussed and agreed upon at meeting held October 24<sup>th</sup>.

HS